

Installation Bulletin 01

Re: TileFlex and CarpetFlex installation in Sun Rooms

Due to extremes in temperature and sunlight conditions encountered in Sun Room applications, the following guidelines should be observed:

Prior to assembling and installing TileFlex or CarpetFlex tiles, the cartons should be opened and left in the room for 24 hours (48 hours in winter) to acclimatize to room conditions.

The ambient room temperature should be 65 – 85 degrees F.

The room to be covered should not exceed 110 degrees F at any time.

The material is a free-floating system and should be trimmed slightly away from the perimeter walls. Refer to chart attached.

Extremely heavy objects – such as bars, hot tubs, entertainment centers, pianos, etc. – should rest directly on the sub floor and be trimmed the same as a fixed wall.



The Original Modular Flooring

TileFlex and CarpetFlex Trim Allowance Table

Temp. (deg. F)	Length (Feet)				
	8	12	16	20	24
90	1/4	1/4	1/4	1/4	1/4
80	1/4	5/16	5/16	5/16	5/16
70	5/16	5/16	3/8	3/8	7/16
60	5/16	3/8	7/16	7/16	1/2
50	3/8	7/16	1/2	9/16	5/8
40	3/8	7/16	9/16	5/8	11/16
30	7/16	1/2	5/8	11/16	3/4

Above represents amount of trim space in inches to allow between tiles and walls (each side), dependent on room length and ambient temperature.

2007 Beechgrove Place • Utica, NY 13501
Phone 315-733-1412 • 800-926-3539 • Fax 315-735-4372